# ALTA VISTA

TAS FLOORING

## HARDWOOD | 5/8" THICK

**Apollo** | HFAVO587AP

**Fermont** | HFAVO587FM

**Santa Rosa** | HFAVO587SR

**Veranda** | HFAVO587VD

### SPECIFICATIONS

| | |
|---|---|
| Construction | Engineered Multi-Layer Parque |
| Species | Engineered European White Oak |
| Dimensions | 7.5" Wide x Random Lengths up to 75" |
| Overall Thickness | 5/8" |
| Attached Pad | N/A |
| Veneer Thickness: | 3.0 mm Sawn-Cut Veneer over Multiply Core |
| Surface Finish | High Performance UV Cured Urethane |
| Design Feature | Thermal Enhanced, Brushed |
| Edge Profile | 4-Sided Bevel |

### INSTALLATION FAST FACTS

- Acclimate product to normal room conditions
- Moisture Content: Is recommended 7% to 9% (Not to exceed 11%)
- Relative Humidity: 40%-55%
- Expansion Space: 7/16" gap
- Recommended Room Temp: 65˚F -75˚F after install

**Read Complete Instructions Before Installing**

tascontract.com

SPEC SHEET
WARRANTY
INSTALLATION & MAINTENANCE
TRIMS, TRANSITIONS & QNOSE

floor score SCScertified

CARB PHASE 2 COMPLIANT

Multi-Length Planks

Thermal Enhanced

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

TAS CONTRACT

Additional specifications, full installation instructions & warranty information available online at **tascontract.com**

T&A supply company, Inc.